


150mm HL-4

150mm GRANULAR 'A'
COMPACTED TO 100% SPMDD

MIN 300mm GRANULAR 'B'
COMPACTED TO 100% SPMDD

COMPACTED GRANULAR MATERIAL OR APPROVED NATIVE FILL

TYPICAL ASPHALT PARKING LOT CONSTRUCTION DETAIL



TYPICAL MUDMAT CONSTRUCTION DETAIL

NOTES:

GENERAL

ALL DIMENSIONS AND ELEVATIONS IN METRIC UNLESS OTHERWISE NOTED.

TOPOGRAPHIC SURVEY COMPLETED BY GM BLUEPLAN ENGINEERING ON JUNE 8, 2021.

PROPERTY BOUNDARIES SHOWN DERIVED FROM PLAN 16M-44, COMPLETED BY HEWITT & MILNE LIMITED ON MAY 21, 2013.

REFER TO ARCHITECTURAL PLANS FOR BUILDING DETAILS AND REPORT ANY DISCREPANCIES.

LOCATIONS OF EXISTING SERVICES ARE APPROXIMATE, AND SHALL BE CONFIRMED PRIOR TO ANY ASSOCIATED EXCAVATION.

ACCESSIBLE PARKING SPACES TO BE CONSTRUCTED IN ACCORDANCE WITH AODA AND CITY OF OWEN SOUND STANDARDS.

ALL WASTE AND RECYCLING RELATED TO SITE MANAGEMENT AND DAILY OPERATIONS WILL BE STORED INSIDE THE BUILDING. NO WASTE DISPOSAL SERVICE WILL BE PROVIDED FOR THE INDIVIDUAL RENTAL UNITS.

BICYCLE PARKING WILL BE PROVIDED ON SITE, AS SHOWN.

SITE LIGHTING IS TO BE WALL-MOUNTED AND PLACED ON SIDE OF BUILDINGS. THE DIRECTION OF LIGHT SHOULD ALLOW MINIMAL TO NO LIGHT AND GLARE ON ADJOINING PROPERTIES.

ALL TOPSOIL TO BE STRIPPED FROM PARKING LOT AREAS AND STOCKPILED ON SITE AND BE USED FOR FINAL LANDSCAPING. SURPLUS TOPSOIL TO BE REMOVED BY THE CONTRACTOR.

ALL LANDSCAPED AREAS WITHIN SUBJECT LANDS TO BE FINISHED WITH 100mm TOPSOIL AND HYDROSEED, UNLESS OTHERWISE NOTED. DISTURBED AREAS WITHIN CITY ROW TO BE FINISHED WITH 100mm TOPSOIL AND SOD.

PARKING SPACES TO BE PAINTED WITH YELLOW LINE PAINT 100mm WIDE.

ACCESSIBLE PARKING SYMBOLS TO BE PAINTED AS PER CITY OF OWEN SOUND STANDARDS.

CONTRACTOR SHALL BE RESPONSIBLE FOR THE COST OF ALL INSPECTIONS, PERMITS AND CERTIFICATES.

ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH CITY OF OWEN SOUND STANDARDS, OPSS AND OBC.

CONTRACTOR/OWNER TO OBTAIN PERMISSION FROM NEIGHBOURING LAND OWNERS TO CROSS PROPERTY BOUNDARY FOR ANY REQUIRED SITE WORKS.

CONSTRUCTION

THE CITY MUST BE NOTIFIED A MINIMUM OF TWO WORKING DAYS PRIOR TO ANY WORK ON A CITY STREET AND APPROPRIATE PERMITS ARE TO BE IN PLACE. THE CONTRACTOR IS RESPONSIBLE TO OBTAIN A STREET OCCUPANCY PERMIT AS NECESSARY.

INSPECTIONS: ALL WORK ON THE CITY RIGHT OF WAY AND EASEMENTS TO BE

INSPECTIONS: ALL WORK ON THE CITY RIGHT OF WAY AND EASEMENTS TO BE INSPECTED BY CITY FORCES PRIOR TO BACKFILLING. ALL WORK RELATING TO WATERMAINS AND SEWERS TO BE INSPECTED BY CITY FORCES WHEN REQUIRED BY THE CITY.

FOR THE WATER SERVICE INSTALLATION, THE CONTRACTOR SHALL PROVIDE EXCAVATION, TRAFFIC CONTROL AND ALL MATERIALS FOR LIVE TAPPING OF THE EXISTING WATERMAIN. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL RESTORATION WORK REQUIRED.

TRANSITIONS WITHIN THE SUBGRADE WITHIN 1.2m FROM THE TOP OF PAVEMENT SHOULD INCLUDE 3H:1V TRANSITIONS.

CONTRACTOR IS RESPONSIBLE TO HAVE IN PLACE EROSION AND SEDIMENT CONTROLS TO KEEP DOWN STREAM DITCHES/SWALES AND CULVERTS FREE FROM ACCUMULATED SEDIMENT PRIOR TO CONSTRUCTION AND DURING ACTIVITY UNTIL VEGETATION IS WELL TAKEN AND PAVING IS COMPLETE.

CONTRACTOR TO ENSURE THAT EXPOSED SLOPES ARE SUFFICIENTLY STABILIZED DURING CONSTRUCTION.

THE CONTRACTOR IS TO TEST SEWERS IN ACCORDANCE WITH THE OBC.

ALL LINE PAINTING AND SYMBOLS SHALL BE APPLIED WITH A MINIMUM OF TWO COATS OF ORGANIC SOLVENT BASED PAINT IN ACCORDANCE WITH OPSS 1712.

ALL WORK SHALL BE CARRIED OUT IN COMPLIANCE WITH THE APPLICABLE HEALTH AND SAFETY ACT AND REGULATIONS FOR CONSTRUCTION PROJECTS.

ALL THE CONSTRUCTION WORK FOR THIS PROJECT SHALL COMPLY WITH THE STANDARD DRAWINGS AND SPECIFICATIONS OF THE CITY OF OWEN SOUND, OBC, OPSS AND OPSD.

THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND PROTECTING ALL UTILITIES DURING CONSTRUCTION. THE CONTRACTOR SHALL ARRANGE FOR ALL EXISTING UTILITIES TO BE LOCATED AND VERIFIED BY EACH UTILITY PRIOR TO COMMENCEMENT OF WORK, ANY VARIANCE IS TO BE IMMEDIATELY REPORTED TO THE ENGINEER. LOST TIME DUE TO FAILURE OF THE CONTRACTOR TO CONFIRM UTILITY LOCATIONS AND NOTIFY THE ENGINEER OF CONFLICTS PRIOR TO CONSTRUCTION WILL BE AT THE CONTRACTORS EXPENSE.

MATERIALS

CONCRETE TO BE 30MPa WITH 7± 1.5% AIR ENTRAINMENT.

ALL TRENCH BACKILL TO BE GRANULAR, COMPACTED TO 95% SPMDD BELOW SUBBASE AND 100% SPMDD FOR SUBBASE AND BASE.

CONTRACTOR SHALL GRADE AND COMPACT EXISTING FILL MATERIAL PRIOR TO PLACING PARKING LOT GRANULARS.

SEWERS

MANHOLES AND CATCH BASIN MANHOLES TO BE PER OPSD 701.010.

CATCH BASINS TO BE PER OPSD 705.010.

DITCH INLET CATCH BASIN TO BE PER OPSD 705.030 WITH 3:1 GRATING PER OPSD 400.000.

PIPE BEDDING PER OPSD 802.010, WITH GRANULAR 'A' BEDDING AND COVER.

SEWER INSTALLATION AND TESTING PER OPSS 410 AND OBC.

ALL STORM SEWERS TO BE HDPE PS320 OR PVC DR-28 SMOOTH WALL OR APPROVED EQUIVALENT.

WATERMAINS

ALL WATERMAINS AND WATER SERVICES TO HAVE 1.8m MINIMUM COVER TO OBVERT OF PIPE.

INDIVIDUAL WATER METER AND DOUBLE CHECK VALVES AS PER CITY STANDARDS.

WATERMAIN INSTALLATION, TESTING AND WORKMANSHIP PER CITY OF OWEN SOUND STANDARDS AND OPSS 701.

CONTRACTOR TO PERFORM WATERMAIN TAPPING. CITY WATER DEPARTMENT TO BE NOTIFIED A MINIMUM OF 2 DAYS PRIOR TO TAPPING

IN THE EVENT OF A PLANNED SERVICE INTERRUPTION, THE CONTRACTOR SHALL

IN THE EVENT OF A PLANNED SERVICE INTERRUPTION, THE CONTRACTOR SHALL PROVIDE A MINIMUM OF 48 HOURS NOTICE TO ALL AFFECTED CUSTOMERS.

CONCRETE THRUST BLOCKS AS PER OPSD 1103.010 (MODIFIED) TO BE INSTALLED ON ALL HORIZONTAL BENDS.

CONCRETE THRUST BLOCKS AS PER OPSD 1103.020 (MODIFIED) TO BE INSTALLED ON

ALL VERTICAL BENDS.

CONCRETE THRUST BLOCKS AS PER OPSD 1105.010 (MODIFIED) TO BE INSTALLED ON ALL FIRE HYDRANTS.

ALL BELL AND SPIGOT JOINTS TO BE RESTRAINED PER MANUFACTURER'S

SPECIFICATIONS.


MECHANICAL JOINTS (GRIP RINGS) TO BE PROVIDED AT ALL FITTING CONNECTIONS.


ALL INSTALLATION AND TESTING TO OBC, NFPA 24, AND TOWN STANDARDS.

THE CONTRACTOR SHALL VERIFY THE SOIL AND GROUNDWATER CONDITIONS AND SHALL PROVIDE APPROPRIATE DRAINAGE FROM THE FIRE HYDRANT AS PER NFPA

PIPE MATERIAL TO BE AWWA C900 DR18 PRESSURE CLASS 235psi; FM APPROVED FOR 150PSI.

CONTRACTOR TO COMPLETE TESTING AND CONTRACTOR'S "MATERIAL AND TEST CERTIFICATE FOR UNDERGROUND PIPING" IN ACCORDANCE WITH NFPA 24-10.10





50mm GRANULAR 'A' OVER GRANULAR 'B'.

REMOVE AND REPLACE EXISTING GRANULAR 'A'
TO DESIGN STANDARD PRIOR TO PAVING.


LANDSCAPED SLOPES TO BE FINISHED WITH
75mm TOPSOIL, SEED AND MULCH UNLESS
OTHERWISE NOTED.

TYPICAL 27th AVENUE EAST ROAD SECTION

NOT TO SCALE

THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARIL SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM HIMSELF OF THE EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM.





GUELPH | OWEN SOUND | LISTOWEL | KITCHENER | LONDON | HAMILTON | GTA 1260 - 2ND AVENUE EAST, UNIT 1, OWEN SOUND, ON N4K 2J3

TEL. 519-376-1805

BLOCK 4 DEVELOPMENT

EAST RIDGE BUSINESS PARK

ANDPET REALTY


NOTES & DETAILS


 DRAWN BY :
 APPROVED BY :
 PROJECT NO. :
 DRAWING NO. :


 E.J.T.
 J.B.S.
 221210
 221210


 DESIGNED BY :
 DATE :
 SCALE :
 1:400


C:C:Drawings\221210spe7.dwg LAYOUT:NOTES T SAVED BY:Ewining, 11/30/2022 11:53:07 AM PLOTTED BY:Ed Twining
































THE POSITION OF POLE LINES, CONDUITS, WATERMAINS, SEWERS AND OTHER

UNDERGROUND AND OVERGROUND UTILITIES AND STRUCTURES IS NOT NECESSARILY SHOWN ON THE CONTRACT DRAWINGS, AND, WHERE SHOWN, THE ACCURACY OF

THE POSITION OF SUCH UTILITIES AND STRUCTURES IS NOT GUARANTEED.

BEFORE STARTING WORK, THE CONTRACTOR SHALL INFORM HIMSELF OF THE

EXACT LOCATION OF ALL SUCH UTILITIES AND STRUCTURES, AND SHALL ASSUME ALL LIABILITY FOR ANY DAMAGE TO THEM.

OROFESSION

J. B. SLOCOMBE



1260 - 2ND AVENUE EAST, UNIT 1, OWEN SOUND, ON N4K 2J3 TEL. 519-376-1805 www.gmblueplan.ca

BLOCK 4 DEVELOPMENT

EAST RIDGE BUSINESS PARK

ANDPET REALTY

NOTES & DETAILS

DRAWN BY :	APPROVED BY :	PROJECT NO. :	DRAWING NO
E.J.T.	J.B.S.	221210	_
DESIGNED BY :	DATE:	SCALE :	
E.J.T.	NOV 30, 2022	1:400	′